

Table of Contents

Abbreviations

Executive Summary	ES-1
-------------------------	------

1	Purpose of the Final Revised BMP	1-1
1.1	Organization of the Final Revised BMP	1-3
2	State of the Basin	2-1
2.1	Basin Boundaries	2-1
2.2	Basin Geology.....	2-3
2.3	Basin Hydrology	2-6
2.3.1	Basin Surface Waters	2-8
2.3.2	Basin Rainfall.....	2-9
2.3.3	Basin Recharge	2-10
2.3.4	Modeling Approach and Results.....	2-10
2.3.5	Key Points	2-10
2.4	Basin Groundwater Levels.....	2-11
2.4.1	Background Groundwater Level Information.....	2-11
2.4.2	Modeling Approach and Results.....	2-11
2.4.3	Key Points	2-12
2.5	Seawater Intrusion	2-14
2.5.1	Principles of Seawater Intrusion	2-14
2.5.2	Seawater Intrusion in the Pajaro Valley.....	2-14
2.5.3	Key Points	2-16
2.6	Land Use	2-18
2.6.1	Historic Land Use	2-18
2.6.2	Current Land Use.....	2-19
2.6.3	Future Land Use.....	2-19
2.6.4	Key Points	2-21
2.7	Water Use.....	2-21
2.7.1	Historic Water Use.....	2-21
2.7.2	Current Water Use	2-23
2.7.3	Future Water Use	2-24
2.7.4	Key Points	2-25
2.8	Basin Sustainable Yield	2-26
2.8.1	Discussion	2-26
2.8.2	Determination of Sustainable Yield.....	2-26
2.8.3	Key Points	2-28
2.9	Water Quality.....	2-29
2.9.1	Constituents of Concern.....	2-29
2.9.2	Current Water Quality in the Pajaro Valley.....	2-31
2.10	Watershed Management Issues.....	2-33
2.11	Description of Problem to be Solved	2-33
2.11.1	Current and Future Basin Deficit.....	2-34
2.11.2	Water Quality Requirements.....	2-34

3	Management Measures	3-1
3.1	Demand Management Options	3-1
3.1.1	Water Conservation	3-1
3.1.2	Water Pricing	3-3
3.1.3	Land Fallowing	3-3
3.2	Pumping Management	3-4
3.3	Summary of Demand and Demand Management	3-4
3.4	Watershed Management.....	3-5
3.4.1	Water Resource Monitoring Program	3-6
3.4.2	Recharge Area Protection Program	3-8
3.4.3	Nitrate Management Program Framework	3-8
3.4.4	Water Metering Program	3-11
3.4.5	Well Management Program	3-12
4	New Water Supply Projects	4-1
4.1	Harkins Slough Project	4-3
4.2	Coastal Distribution System	4-6
4.3	Recycled Water (4,000 AFY) with Blending Facility	4-9
4.4	Recycled Water Project (6,000 AFY) with Southeast Dunes Recharge Basin	4-13
4.5	Recycled Water Project (7,700 AFY) with Harkins Slough and North Dunes Recharge Basins.....	4-16
4.6	Murphy Crossing with Recharge Basins.....	4-19
4.7	Watsonville Slough with North Dunes Recharge Basin	4-22
4.8	College Lake Project with Pinto Lake Diversion	4-24
4.9	Expanded College Lake Project with Pinto Lake, Corralitos Creek, Harkins Slough, Watsonville Slough Diversions, and Aquifer Storage and Recovery	4-28
4.10	Import Water Project – Central Valley Project (CVP) with Various Storage Alternatives.....	4-33
4.10.1	Draft BMP 2000 – 60-inch Import Water Project with Inland Distribution System and Supplemental Wells	4-35
4.10.2	54-inch Import Water Pipeline with Aquifer Storage and Recovery (ASR).....	4-38
4.10.3	42-inch Import Water Pipeline with Aquifer, Storage, and Recovery	4-39
4.10.4	Out-of-Basin Banking Option.....	4-42
4.11	Bolsa De San Cayetano with Pajaro River Diversion.....	4-43
4.12	Seawater Desalination.....	4-46
4.13	Summary	4-48
5	Basin Management Plan Strategies.....	5-1
5.1	BMP 2000 Alternative	5-3
5.2	Local-Only Alternative	5-10
5.3	Modified Local Alternative.....	5-19
5.4	Modified BMP 2000 Alternative	5-26

5.5	Non-Economic Comparison of Alternative Strategies	5-33
5.5.1	Can Meet Existing and Future Water Needs.....	5-33
5.5.2	Limited Dependence on Out-of-Basin Water Supplies	5-34
5.5.3	Minimizes Regulatory Hurdles.....	5-34
5.5.4	Meets Water Quality Goals.....	5-34
5.5.5	Economic Impact	5-34
5.5.6	Summary of Criteria Comparison.....	5-35
5.6	Cost Comparison of Alternatives.....	5-36
5.7	Cost Comparison with Future Water Use	5-38
5.8	Summary Comparison of Alternatives.....	5-39
6	Revise Basin Management Plan Recommendation	6-1
6.1	Draft BMP and Selection Process for Recommended Alternative	6-1
6.2	Recommended Alternative.....	6-2
6.3	Water Balance.....	6-6
6.4	Operational Strategy	6-7
6.5	Estimated Costs.....	6-9
6.6	Potential Future Phases	6-10
6.7	Summary of Key Points	6-11
7	Implementation Plan for Recommended Alternative	7-1
7.1	Phase 1	7-2
7.1.1	Conservation Program Implementation	7-2
7.1.2	Harkins Slough Project with Harkins Slough Recharge Basin and Supplemental Wells and Connections Implementation	7-3
7.1.3	Harkins Slough Coastal Distribution System Implementation	7-3
7.1.4	Watershed Management Programs	7-3
7.1.4.1	Water Metering Program	7-3
7.1.4.2	Water Resources Monitoring Program	7-4
7.1.5	CVP Contract Assignment from Mercy Springs Water District for the Import Water Project	7-4
7.2	Phase 2	7-4
7.2.1	Coastal Distribution System Implementation	7-5
7.2.2	54-inch Import Water Project with Out-of-Basin Storage Implementation	7-7
7.2.3	Recycled Water Project Implementation	7-9
7.2.4	Watershed Management Programs	7-11
7.2.4.1	Nitrate Management Program.....	7-11
7.2.4.2	Wells Management Program.....	7-12
7.2.4.3	Recharge Area Protection Program	7-12
7.3	Potential Future Phases	7-12
7.3.1	Aquifer Storage and Recovery of CVP Water (ASR)	7-12
7.3.2	Inland Distribution System (IDS).....	7-13
7.3.3	Watsonville Slough Project with North Dunes Recharge Basin.....	7-13
7.3.4	College Lake Project Implementation	7-14
7.3.5	Murphy Crossing Project Implementation.....	7-14

7.4	Summary of Key Points	7-14
8	Proposed Rate Plan for Recommended Alternative.....	8-1
8.1	Existing Rates and Restrictions	8-1
8.2	Alternative Rate Structures	8-1
8.3	Alternative Rate Evaluations	8-3
8.4	Recommended Rate Plan	8-4
References		

List of Tables

Table ES-1: Recommended Alternative Cost Estimate (Phase 1 and 2).....	ES-2
Table ES-2: Required Additional Water Supplies, Assuming Water Conservation.....	ES-8
Table ES-3: Projects Selected for Each Basin Management Strategy.....	ES-13
Table ES-4: Summary Comparison of the Basin Management Strategies.....	ES-16
Table 2-1: Water Bearing Units of the Pajaro Valley (Youngest to Oldest).....	2-4
Table 2-2: Summary of Land Use (Model Area).....	2-18
Table 2-3: Summary of Agricultural Land Use (Model Area).....	2-19
Table 2-4: PVWMA Population Projections and Urban Water Use.....	2-25
Table 2-5: Current and Future Water Demand and Groundwater Pumping.....	2-25
Table 2-6: Identification of Required Supplemental Supplies.....	2-28
Table 2-7: CCRWQCB Irrigation Water Quality Guidelines.....	2-30
Table 2-8: Current and Future Basin Water Use and Current Sustainable Supply.....	2-34
Table 2-9: Revised BMP Irrigation Water Quality Objectives.....	2-34
Table 3-1: Conservation Present Worth Analysis.....	3-2
Table 3-2: Identification of Required Supplemental Supplies with Conservation.....	3-5
Table 4-1: Summary of New Water Supply Components.....	4-2
Table 4-2: Harkins Slough Project Cost Estimate.....	4-5
Table 4-3: Coastal Distribution System Cost Estimate.....	4-8
Table 4-4: Watsonville Wastewater Treatment Facility Discharge Limits.....	4-10
Table 4-5: Recycled Water Project Cost Estimate (Conventional/Chlorination).....	4-12
Table 4-6: Recycled Water Project with Southeast Dunes Recharge Basin Cost Estimate.....	4-15
Table 4-7: Recycled Water Project with Harkins Slough and North Dunes Recharge Basin Cost Estimate.....	4-18
Table 4-8: Murphy Crossing Project Cost Estimate.....	4-21
Table 4-9: Watsonville Slough Cost Estimate.....	4-23
Table 4-10: College Lake with Pinto Lake Diversion Project Cost Estimate.....	4-27
Table 4-11: Expanded College Lake Project with Pinto Lake, Corralitos Creek, Harkins Slough, Watsonville Slough, and ASR Cost Estimate.....	4-32
Table 4-12: Import Water Projects with Associated Storage Cost Estimate.....	4-41
Table 4-13: Bolsa De San Cayetano with Pajaro River Diversion Cost Estimate.....	4-45
Table 5-1: Comparison of Alternatives.....	5-2
Table 5-2: BMP 2000 Alternative Water Balance Objective.....	5-5
Table 5-3: BMP 2000 Alternative Cost Estimate.....	5-8
Table 5-4: Additional Facilities Required to Meet 2040 Agricultural and Urban Demand.....	5-9
Table 5-5: PVI GSM Modeling Input to Achieve Basin Balance for LOA.....	5-11
Table 5-6: LOA Water Balance Objective.....	5-13
Table 5-7: Local-Only Alternative Cost Estimate.....	5-16
Table 5-8: Modified Local Alternative Water Balance Objective.....	5-21
Table 5-9: Modified Local Alternative Cost Estimate.....	5-24
Table 5-10: Additional Facilities Required to Meet 2040 Agricultural and Urban Demand.....	5-25
Table 5-11: Modified BMP 2000 Alternative Water Balance Objective.....	5-28
Table 5-12: Modified BMP 2000 Cost Estimate.....	5-31
Table 5-13: Additional Facilities Required to Meet 2040 Agricultural and Urban Demand.....	5-32
Table 5-14: Alternative Ranking Based on Identified Criteria.....	5-35
Table 5-15: Summary of Alternative Cost Estimates.....	5-37
Table 5-16: Summary Comparison of the Basin Management Strategies.....	5-40
Table 6-1: New Water Supplies Developed by Recommended Alternative.....	6-6
Table 6-2: Recommended Alternative Cost Estimate (Phase 1 and 2).....	6-9
Table 6-3: Resource Allocation for Conservation and Watershed Management Programs.....	6-10

List of Figures

Figure ES-1: Location of Area Impacted by Seawater Intrusion	ES-6
Figure ES-2: Location of Water Supply Projects.....	ES-14
Figure 2-1: PVWMA Service Area and PVI GSM Model Area	2-2
Figure 2-2: Pajaro Valley Surface-Level Geologic Units.....	2-5
Figure 2-3: Annual Streamflow Pajaro River at Chittenden	2-8
Figure 2-4: Annual Rainfall in Watsonville, CA.....	2-9
Figure 2-5: Groundwater Levels in the Pajaro Valley.....	2-13
Figure 2-6: Seawater Intrusion	2-14
Figure 2-7: Seawater Intrusion Equilibrium.....	2-15
Figure 2-8: Location of Area Impacted by Seawater Intrusion	2-17
Figure 2-9: Land Use in the PVWMA Service Area.....	2-20
Figure 2-10: Pajaro Valley Historic Urban Water Use.....	2-22
Figure 2-11: Pajaro Valley Historic Annual Agricultural Water Use	2-23
Figure 2-12: Seawater Intrusion with Coastal Versus Inland Pumping.....	2-27
Figure 3-1: Nitrate Levels in the Pajaro Valley.....	3-10
Figure 4-1: Harkins Slough Project	4-3
Figure 4-2: Coastal Distribution System	4-7
Figure 4-3: Recycled Water with Blending Facility.....	4-9
Figure 4-4: Recycled Water Project with Southeast Dunes Recharge Basin	4-13
Figure 4-5: Recycled Water Project with Harkins Slough and North Dunes Recharge Basin	4-17
Figure 4-6: Murphy Crossing Project.....	4-19
Figure 4-7: Watsonville Slough Project	4-22
Figure 4-8: College Lake with Pinto Lake Project	4-24
Figure 4-9: Expanded College Lake Dam with Pinto Lake, Corralitos Creek, Harkins Slough, Watsonville Slough, and Aquifer Storage and Recovery	4-29
Figure 4-10: Import Water Pipeline Alignment.....	4-34
Figure 4-11: Inland Distribution System.....	4-36
Figure 4-12: Bolsa De San Cayetano with Pajaro River Diversion Project	4-43
Figure 5-1: Map of BMP 2000 Alternative	5-4
Figure 5-2: BMP 2000 Alternative Flow Schematic	5-6
Figure 5-3: Map of Local Only Alternative.....	5-12
Figure 5-4: Local-Only Alternative Flow Schematic	5-14
Figure 5-5: Map of Modified Local Alternative.....	5-20
Figure 5-6: Modified Local Alternative Flow Schematic.....	5-23
Figure 5-7: Map of Modified BMP 2000 Alternative	5-27
Figure 5-8: Modified BMP 2000 Flow Schematic	5-29
Figure 6-1: Recommended Alternative (Phase 1 and 2).....	6-5
Figure 6-2: Flow Schematic for the Recommended Alternative (Phase 1 and 2)	6-8
Figure 7-1: Coastal Distribution System Implementation Schedule	7-6
Figure 7-2: Import Water Project Implementation Schedule	7-8
Figure 7-3: Recycled Water Project Implementation Schedule.....	7-10